No.	Items of work	Unit	Rate	Quantity	Rate to be tendered
	III. Constructing a masonry weir at the left flank about 65 ft. long with crest at R.L. 53·00.		Rs. a. p.		
1	Dismantling the old masonry which is in a damaged condition	L. S.	..	..	
2	Earthwork excavation for foundation in chettu soil	C.yd.	0 4 0	81	
3	Burnt stone jelly concrete in surki mortar ..	C.ft.	0 4 0	293	
4	Burnt stone in surki mortar	,,	0 5 0	814	
5	Burnt stone slabs 6″ thick dressed and fixed ..	Sq.ft	0 5 0	298	
6	Pointing with surki mortar	Sqr.	2 0 0	8·44	
7	Providing joggle joints	Each	0 8 0	8	
8	Rough stone apron	C.yd.	1 8 0	39	
	Total ..				

R. TIPPAIYA,
Executive Engineer.

KRISHNARAJASAGAR DIVISION.

Notification No. 2967, *dated 23rd March* 1939.

The following Mysore Government Savings Bank Pass Books are remaining unclaimed in this Division, for some years. The depositors or their legal heirs may apply to this office for obtaining the pass books after producing satisfactory proof of identity, on or before the 20th April 1939.

Savings Bank Pass Book No. 5525 in favour of Mr. V. A. Sarangapani Mudaliar, Sub-overseer.

Savings Bank Pass Book No. 6554 in favour of Mr. H. N. Ramaswami.

G. SESHAGIRI ROW,
Executive Engineer.

HASSAN DIVISION.

Notification dated 26th March 1939.

1. Sealed tenders will be received at the Office of the Executive Engineer, Hassan Division, Hassan, up to 17th April 1939, for restoring Sanagere Ranganakere, Arsikere Taluk.

2. Tenders in the prescribed form obtainable in the Office of the Executive Engineer, Hassan Division, Hassan, should be addressed to the Executive Engineer, Hassan Division Hassan, and should be superscribed as "Tender for restoring Sanagere Ranganakere, Arsikere, Taluk." The name of the tenderer should also be superscribed on the sealed cover.

3. Each tender must be accompanied by a deposit of Rs. 550 only in cash as earnest money. The earnest money of the successful tenderer will be retained as cash security for the due fulfilment of the contract. (Cash amount will not carry any interest.) In case of the acceptance of the tender, an addition of the five per cent of the estimated amount as security deposit should be paid at the time of executing the agreement in the Public Works Department.

4. The tenders will be opened in the presence of such tenderers who wish to be present on the date of opening. The final acceptance of the tender will rest with the Executive Engineer, Hassan Division, who does not bind himself to accept the lowest or any tender, or to assign any reasons whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Office of the Executive Engineer in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute the agreement in the departmental schedule contract form for the due fulfilment of the contract.

6. Failure to comply with the condition 5 above, or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. Copies of contract documents, estimates and drawings may be seen at any time at the Office of the Executive Engineer, Hassan Division, Hassan, on all working days, between 11 A.M. and 5 P.M.

8. Specific rates should be given for each item in the schedule and the rates should be in rupees, annas and pies and expressed in words and figures.

9. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates tendered should include all such lumpsum items.

10. No alterations which are made by the tenderers in the contract documents in the nomenclature of the sanctioned sub-heads will be recognised, and if corrections are made, the tenders will be liable to rejection.

11. There should be no corrections or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

12. No reference should be made to the Public Works Department current schedule of rates.

13. On the event of the tender being submitted by a firm, it must be signed separately and severally by each member therefor or in the event of absence of any partner, it must be signed on his behalf by a person holding power-of-attorney authorising him to do so.

14. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates to be proposed by the Executive Engineer, Hassan Division, Hassan, and approved by the Superintending Engineer, shall be final and legally binding on the tenderer.

15. The quantities as estimated are only approximate and are liable to alterations, omissions, deductions, or additions at the discretion of the Executive Engineer, or his representative. The tendered rates will hold good for any quantity whether higher or lower than those estimated for.

16. The work should be completed as per departmental specifications for different items and handed over to Public Works Department by the end of December 1940, failing which, the Executive Engineer may, at his discretion, levy a penalty up to Rs. 500 which will be recovered from the contractor's outstandings for the period exceeded by him till the work is completed and handed over.

17. In all matters of dispute of any kind, not specially provided for in the agreement or of rates, penalties, measurements, quantity of work, etc., the decision of the Executive Engineer, shall be final and legally binding.

18. The earnest money for rejected tenders will be returned on surrender of the receipts originally granted, along with an application to the Executive Engineer, Hassan Division, Hassan.

19. No claims for damages for delays caused by officers of the department in the execution of work will be considered, whatever may be the reason for such delays. Contractors should bear this in mind when tendering for work. Extension of time due to delays caused by the departmental officers will be, however, considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools, plant and machinery that will be supplied by the department in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer, and the tenderer will pay the hire, etc., on machinery at the prescribed per cent per annum of the booked value of the tools and plant supplied from the date of taking over of tools and plant from the Stores to the date of return to the Stores, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractors should arrange for the payment of royalty and tolls

Abstract estimate for restoring Sanagere Ranganaikanakere, Arsikere Taluk (Reg. No. 131).

No.	Items of work	Unit	Rate	Quantity	Cost
	Bund.		Rs. a. p.		Rs.
1	Turfing the slopes both front and rear with garike or Mani turf	Sq.yd.	0 1 0	1,289	
2	Providing rough stone revetment to bund ..	C.yd.	1 12 0	103	
3	Removing and resetting old stone revetment with new jelly packing, etc.	,,	0 12 0	100	
4	Providing grade stones with bed slabs and index stones including cutting figures, painting with white lead, Japan, etc.	Each	2 8 0	41	
5	Providing and fixing Reg. No. stone including cutting figures painting, etc., complete ..	,,	4 0 0	1	
6	Providing and fixing B. M. stones including cutting figures, painting, etc., complete	,,	2 8 0	2	
	Constructing Left Waste Weir.				
1	Earthwork draft clearing in gravelly soil mixed with disintigrated soft rock to R. L. 46·00 ..	C.yd.	0 5 0	197	
2	Earthwork—Approach clearing in stiff soft rock ..	,,	0 6 0	1,416	

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
3	Earthwork Excavation for foundation in stiff soft rock	C.yd.	0 6 0	331	
4	Stone jelly concrete in cement mortar 1 : 6 ..	C.ft.	0 4 6	448	
5	Size stones in cement mortar 1 : 6	,,	0 6 6	715	
6	Burnt stone slabs 6" thick dressed and fixed ..	Sq.ft.	0 8 0	397	
7	Providing pin slabs to be fixed in concrete in cement mortar	,,	0 12 0	68	
8	Cement pointing to exposed masonry	Sqr.	3 8 0	6.00	
9	Rough stone apron with jelly packing and wedging.	C.yd.	1 12 0	68	
10	Removing and resetting old apron with new jelly packing and wedging	,,	0 12 0	79	
11	Providing joggle joints	Each	1 0 0	11	
	Constructing Right Waste Weir.				
1	(*a*) Earthwork :—Approach and draft clearing up to R. L. 46.00 in all soils	C.yd.	0 4 0	1,219	
	(*b*) Do in soft rock exposed ..	,,	0 6 0	563	
2	(*a*) Earthwork excavation in hard gravelly soil ..	,,	0 4 0	1,028	
	(*b*) Do in soft rock	,,	0 6 0	1,368	
3	Stone jelly concrete in cement mortar 1 : 6 ..	C.ft.	0 4 6	2,114	
4	Size stones in cement mortar 1: 6	,,	0 6 6	5,083	
5	Burnt stone slabs 6" thick dressed and fixed ..	S.ft.	0 8 0	568	
6	Cement concrete slab over toe wall including cement plastering	C.ft.	0 14 0	127	
7	Cement pointing to masonry	Sqr.	3 8 0	24·41	
8	Providing joggle joints	Each	1 0 0	31	
9	Rough stone apron including jelly packing and wedging	C.yd.	1 12 0	1,013	
10	Removing and resetting old stone work with new jelly packing, etc.	,,	0 12 0	178	
11	Jelly filling below apron with one mile lead ..	,,	1 0 0	222	
	Repairing Sluice No. I.				
1	Cutting open the bund for examining the masonry with refilling, watering and consolidation, etc.	C.yd.	..	..	

P. SUBBA RAO,
Executive Engineer.

KADUR DIVISION.

Notification dated 27th March 1939.

1. Sealed tenders will be received at the Office of the Executive Engineer, Kadur Division, Chikmagalur, up to 3 P.M. on 15th April 1939 for the work of constructing drains in Chikmagalur town during 1938-39 and 39-40.

2. Tenders in the prescribed form obtainable from the Office of the Executive Engineer, Kadur, Division, should be addressed to the Executive Engineer, Kadur Division, Chikmagalur, in a sealed cover and superscribed as "Tender for the work of constructing drains in Chikmagalur town during 1938-39 and 1939-40." The name of the tenderer should also be superscribed on the top of the cover.

3. Each tender must be accompanied by a Treasury challan for Rs. 1,075 (Rupees one thousand and seventy five only) for having credited this earnest money to 17 (a) P. W. Deposits in any approved Government Treasury. The earnest money of the successful tenderer will be retained as security deposit for the due fulfilment of the contract. Such a deposit will not carry any interest. Tenders unaccompanied by earnest money will not be accepted.

4. The tenders will be opened in the presence of such tenderers who wish to be present on 15th April 1939 at Chikmagalur. The final acceptance of the tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Executive Engineer's Office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute an agreement in the departmental Schedule Contract Form for the due fulfilment of the contract.